

Scope of Work

Tartesso: Unit 1

Rubberized Crack Seal- Clean out cracks using a vacuum system and in accordance to PM10 Dust Control Regulations (no blowers allowed) then a hot application of Crafco Poly Flex Type 3 (or equal) asphalt based product to be applied as specified in Job Order Contract Technical Specifications (Section 2.2). For cracks wider than 1 ½ " and over 2" in depth an Asphalt Concrete Crack Mastic (or equal) will be used without milling or routing as specified in Job Order Contract Technical Specifications (Section 2.2).

- **Asphalt Emulsion Seal Coat-** Contractor is responsible for removal , replacement and installation of any missing (RPM's) with new Raised Pavement Markers (RPMs) in accordance to M.U.T.C.D. standards and as specified in Job Order Contract Technical Specifications (Section 2.11.5) Streets will be swept to ensure surface is thoroughly dried and free of any debris or oils prior to application. Application of PMM-RTU Asphalt Emulsion Sealcoat (or equal) to be applied as specified in Job Order Contract Technical Specifications (Section 2.12). In all cases; curb shields should be used to protect adjacent concrete, landscaping and other structures from over-spray.
- **Pavement Markings-**Re-stripe as existing traffic markings after asphalt treatment as specified in Job Order Contract Technical Specifications (Section 2.14). Existing Thermoplastic Pavement Markings/Stencils require temporary paint markings during Asphalt Seal Coat curing time. Curing time should be no less than thirty days unless otherwise approved for earlier striping by City of Buckeye Inspector. After curing time, thermoplastic applications would be applied in accordance to Job Order Contract Technical Specifications (Section 2.15) and City of Buckeye Standards.
- **Contractor's Requirements-** Contractor is responsible for community outreach (i.e.- door knob hangers, fliers, etc.), traffic control and mapping of scheduled work to coordinate with Solid Waste Services. Contractor is to provide pricing in Square Yards Rate.

